



Hooghly-Chinsurah-Municipality

Mahendra Mitra Road, Pipulpati, PO & Dist. - Hooghly, West Bengal.
Tel: 2680-2899/2319, TeleFax.: (033) 2680-6091

TENDER NOTICE NO- 24/2022-23/WW-SD

DATE- 27/06/2022

Sealed tenders are invited from the bonafide & experienced Agency for the Laying(Replacement) of 100mm D.I, 110 mm & 90mm UPVC pipeline at Sonatuli ward -07, Immambazar, in ward- 09, Manna Bagan ward-10, Bairagi gali & Kadamtala ward-13, S & B Ghat ward-26 & 28 under under H.C.M. The rate should be quoted inclusive all taxes and other charges in the official letterhead pad both in figure and word mentioning clearly the rate per unit. No overwriting in the rate will be entertained. No transport cost will be allowed in this respect. Tender papers should be dropped in the "Tender Box kept with the Office Superintendent as per following programmed. Tenders sent by registered Post, within the time will also be entertained.

1. Last date for submission of tender paper.

Sealed cover containing the tender papers should be superscripted Tender for Laying(Replacement) of 100mm D.I, 110 mm & 90mm UPVC pipeline at Sonatuli ward -07, Immambazar, in ward- 09, Manna Bagan ward-10, Bairagi gali & Kadamtala ward-13, S & B Ghat ward-26 & 28 under H.C.M. The last date of receipt of Tender is **07-07-2022** upto 2 p.m.

Tender will be opened on the same day at 3 p.m.

Tenderers or their authorized representatives may remain present at the time of opening of tender at the chamber or the Finance officer. **Fund- 15Th F.C. Tied Grand.**

2. The following documents are to submitted with the Tender.

- Copy of Valid Trade License
- Copy of GSTIN Certificate & Pan
- Experience for the same type of work.

3. Earnest money **Rs. 9300/-** should be deposited in cash is to be deposited with the cashier of the municipality or may deposit Demand Draft drawn in favor of the Chairperson HCM on any schedule Indian Bank at the time of submitting tender and the money receipt will be attached with the tender paper. The rate will remain valid for one year from the date of the execution of the agreement with the undersigned.

The Chairperson of the Municipality reserves the right to reject any tender in part or full without assigning any reason. He reserves the right to distribute the work order among two or more suppliers. In case of any dispute decision of the chairman will be final and binding upon all.

SL.N O	DESCRIPTION OF METERIALS /work	QUANTITY	Basic Rate (Rs.)	C.GST	S.GST	TOTAL RATE
1.	Excavation trench including dismantling of Concrete Road for laying of D.I pipes 100 mm OD with Specials, in all sorts of soil including mixed with boulders road subgrade and its flanks preparing the bottom surface for continuous bedding of pipeline & laying, specials and valves in proper alignment with bailing out of water if required induding carrige of spedals from local store upto actual site oi work induding loading, unloading & stacking within 25 km cutting of pipes where necessary keeping a clear cover at least 1.00 Metre between G.L. & top of the pipe and back filling the trenches with earth (using excavated earth) in layers with proper watering & compaction of each layer to original condition. Lowering of the pipes and spedals in excavated trenched aligning & jointing of pipe by chemical solvent induding cost of materials	48 mtrs				
2.	Excavation trench including dismantling of Concrete Road for laying of UPVC pipes Class-III 110 mm OD with Specials, in all sorts of soil including mixed with boulders road subgrade and its flanks preparing the bottom surface for continuous bedding of pipeline & laying, specials and valves in proper alignment with bailing out of water if required induding carrige of spedals from local store upto actual site oi work induding loading, unloading & stacking within 25 km cutting of pipes where necessary keeping a clear cover at least 1.00 Metre between G.L. & top of the pipe and back filling the trenches with earth (using excavated earth) in layers with proper watering & compaction of each layer to original condition. Lowering of the pipes and spedals in excavated trenched aligning & jointing of pipe by chemical solvent induding cost of materials	314 MTR				

Continued.....

Continuation.....

3.	Excavation trench including dismantling of Concrete Road for laying of UPVC pipes Class-III 90 mm OD with Specials, in all sorts of soil including mixed with boulders road subgrade and its flanks preparing the bottom surface for continuous bedding of pipeline & laying, specials and valves in proper alignment with bailing out of water if required including carriage of specials from local store upto actual site of work including loading, unloading & stacking within 25 km cutting of pipes where necessary keeping a clear cover at least 1.00 Metre between G.L. & top of the pipe and back filling the trenches with earth (using excavated earth) in layers with proper watering & compaction of each layer to original condition. Lowering of the pipes and specials in excavated trenches aligning & jointing of pipe by chemical solvent including cost of materials	84 MTR				
4.	House connection shifting & stand post shifting- WITH SUPPLY OF 20 MM G.I PIPE , SOCKET ,UNION,NIPPLE, ETC.	103 NOS				
5.	4" INTER CONNECTION, A.C PIPE WITH [4" C.I CAP]LABOUR FITTING CHARGE	2 NOS				
6.	5" INTER CONNECTION,C.I PIPE WITH [4" C.I CAP]LABOUR FITTING CHARGE	1 NO				
7.	6" INTER CONNECTION,C.I PIPE WITH [4" C.I CAP]LABOUR FITTING CHARGE	3 NOS				
8.	weat connection ms saddle on running mainall complete excluding cost of ms saddle and earth WORK{12" SADDLE INTER CONNECTION,C.I PIPE }	1 NO				
9.	C.I SADDLE	65 NOS				
10.	10 MM AKB FERRULE	5 NOS				
11.	4" INTER CONNECTION WITH 100 MM DIA D.I PIPE -2 NOS & LAYING 100 MM DIA D.I PIPE -9 MTR INCLUDING EXCAUTION OF EARTH ,CUTTING AC/ D.I PIPE & ,FILLING FOUNDATION WITH EARTH OBTAINED FROM THE TRENCHED AND ALLIGHT WORK [100 MM X 100 MM TEE 2 NOS TO BE SUPPLIED BY DEPARMENT	2 NOS				
13.	MAKING LIGHTING ARRANGEMENT FOR CONTINUATION WORK DURING NIGHT & MAKING BARRICDING OF EXCAVATION	1 NOS				
14.	CLEARING DISTRIBUTION PUIPE LINE BY OPENING VALVE OF ANY SIZE	2 NOS				
15.	DEWATER BY PUMP { 4 H.P -8 HR -32H.P -HRS}	32H.P -HRS				
16.	100 MM DIA D.I PIPE SUPPLY AND FITTING FIXING	9 MTR				
17.	100 MM J.P COUPLING SUPPLY AND FITTING FIXING	6 NOS				
18.	4" TITON RUBBER RING SUPPLY AND FITTING FIXING	2 NOS				
19.	SUPPLY OF 20 MM G.I PIPE SUPPLY AND FITTING FIXIN	38 MTR				

MEMO NO-3617/20 /WW/SD

DATED- 27/06/22

50K
CHAIRMAN/EXECUTIVE OFFICER
HOOGHLY CHINSURAH MUNICIPALITY

Copy forwarded for information with a request to arrange for publishing the Quotation paper by his notice board-
1.Sabadihati, Hooghly Zillah Parishad. 2. The District Magistrate ,Hooghly, 3.The Asstt. Engineer, P.H.E, Chinsurah Sub Division. 4. The Mayour , Chandannagar Mpl.Corporation. 5. The Chairman , Bansberia Municipality. 6. The asstt. Engineer , PWD.Hooghly Sub Division,Chawk Bazar,Hooghly. 7. The Chairman , Pr. School Board, Pipulpati, Hooghly. 8. The Director, DDLB, Pipulpati,Hooghly. 9. Consumer Affairs Dept. Joraghat, Hooghly. 10.Executive Engineer,MED,Anupam Bhaban, Hooghly. 11. The DICO (Rabindra Bhaban,Chinsurah, Hooghly)12. Executive Officer, HCM., 13. Finance Officer ,HCM , 14. The Accountant , HCM,15. AHC/HCM 16.The CIC/Water,HCM . 17. SAE/Water, HCM ,,18.Sri Partha Das/PS/ASK/HCM. 19.Website of HCM (www.hcm.net.in) 20.Office Notice Board.

CHAIRMAN/EXECUTIVE OFFICER
HOOGHLY CHINSURAH MUNICIPALITY